



Notes:

ALL TRAFFIC MANAGEMENT TO BE DESIGNED AND INSTALLED IN ACCORDANCE WITH TSM CHAPTER 8, INCLUDING SIZE OF TEMPORARY SIGNS.

SIGNS SHOULD BE PLACED WHERE THEY WILL BE CLEARLY SEEN, AVOID VISIBILITY OBSTRUCTION AND CAUSE MINIMUM INCONVENIENCE TO DRIVERS/ CYCLISTS.

Qty: 5 Ref: 13.9 Schedule 13-9: Temporary Information	
Qty: 2 Ref: 13.9 Schedule 13-9: Temporary Information	
Qty: 2 Ref: 13.9 Schedule 13-9: Temporary Information	
Qty: 2 Ref: 13.9 VP01 Schedule 13-9: Temporary Information	
Qty: 2 Ref: 2702 End of temporary diversion route	
Qty: 3 Ref: 2702 Start of temporary diversion route	
Qty: 1 Ref: 2702 Start of temporary diversion route	
Qty: 3 Ref: 2703 Direction of temporary diversion route from junction ahead	
Qty: 3 Ref: 2703 Direction of temporary diversion route from junction ahead	
Qty: 4 Ref: 2703 Direction of temporary diversion route from junction ahead	
Qty: 3 Ref: 2704 Direction of temporary diversion route	
Qty: 3 Ref: 2704 Direction of temporary diversion route	
Qty: 1 Ref: 572 Distance ahead to hazard	
Qty: 1 Ref: 572 Distance ahead to hazard	
Qty: 1 Ref: 572 Distance ahead to hazard	
Qty: 8 Ref: 7001 Road works ahead	
Qty: 4 Ref: 7010-FP-13-9 Nature of temporary hazard ahead - Road Closed	
Qty: 12 Ref: 7010-FP-13-9 Nature of temporary hazard ahead - Road Ahead Closed	
Qty: 5 Ref: 7105 Lane closure barrier	

C01	02/04/25	Original	NP	OW	NF
Rev	Date	Description	Drm	Chkd	App
Revisions					

Client

SUFFOLK HIGHWAYS
www.suffolk.gov.uk/highways

Drawing Originator

MILESTONE INFRASTRUCTURE
A part of MGroup Services

Phoenix House,
3 Goddard Road,
Ipswich,
Suffolk IP1 5NP

This drawing is copyright of Milestone Infrastructure and shall not be reproduced without prior written permission

Drawing Status

For Information

Title

C659 Ashfield Green, Wickhambrook 276124

Notes:

Road Closure

Diversion route

Project Name

Road Closure + Diversion

Sheet Size	Scale	Drawn by	Checked by	Approved by
A3	NTS	NP	OW	NF
Drawn Date	Checked Date	Approved Date		
02/04/25	02/04/25			

Drawing Number

276124-SH-TTM-DR-CH-0101

Status

S2

Rev

C01